# 2020 BEACH ASSESSMENT UPDATE: Town of Southern Shores, NC

KEN WILLSON, SENIOR PROGRAM MANAGER

kwillson@coastalprotectioneng.com



**JANUARY 21, 2021** 

#### **Background:**

- December 2017 Initial Town-wide beach profile survey conducted
- March 2018 Initial Beach Assessment provided
- December 2018 Vulnerability Analysis and Beach Management Plan provided
- May 2019 Second Town-wide beach profile survey conducted
- September 2019 Updated volumes and recommendations from the 2018 Plan (2019 Beach Assessment)

#### **Background (continued):**


 Dec. 2019 – Jan. 2020: Town requested update of project goals and development of additional alternatives to include entire Town

#### Project Goals:

- 1. Provides a reasonable level of storm damage reduction to public and private development
- 2. Mitigates long-term erosion that could threaten public and private development, recreational opportunities, and biological resources
- 3. Maintains a healthy beach that **provides sufficient useable beach** and supports valuable shorebird and sea turtle nesting habitat
- June 2020 Third Town-wide beach profile survey conducted
- July 2020 Town Authorized CPE to conduct permitting and design of the proposed beach nourishment project



#### **Project Area:**




PROTECTION


ENGINEERING

#### **Project Area:**






#### **Project Area:**



PROTECTION


ENGINEERING


## **Shoreline Change:**





## **Volume Change:**






## **Shoreline / Volume Change:**


- Three (3) Sections Referenced:
  - North Section North Town boundary to 3<sup>rd</sup> Ave.
  - ➤ Central Section 3<sup>rd</sup> Ave. to approx. 400 ft. south of Chicahauk Trl.
  - South Section Approx. 400 ft. south of Chicahauk Trl. to southern Town boundary
- Town Wide Changes between Dec. 2017 and June 2020
- Central and South Sections Changes between Oct. 2006 to June
   2020
- From 9<sup>th</sup> Ave. to Northern Town Boundary Changes between Sept.
   2013 and June 2020



#### **Shoreline Change (Update):**

- North Section:
  - > Average shoreline change rate of -2.3 ft./yr. between Dec. 2017 and June 2020
  - Average shoreline change rate of -1.3 ft./yr. between Sept. 2013 and June 2020 (6.75 years) along the northern 2,000 feet of Town (Area north of 9<sup>th</sup> Ave.)
- Central Section Average shoreline change rate of -2.3 ft./yr (Dec. 2017 to June 2020) and -1.3 ft./yr (Oct. 2006 to June 2020)
- South Sections Average shoreline change rate of -10.8 ft./yr (Dec. 2017 to June 2020) and -1.1 ft./yr (Oct. 2006 to June 2020) Note: Includes beach nourishment





Approximate Location of +12 Ft. Contour



#### **Table from Beach Management Plan Addendum A**

| Beach Section  | Profile Stations   | Average Useable Beach<br>Width |  |
|--|--------------------|--------------------------------|--|
| Town of Southern Shores from 3rd<br>Avenue South to Southern Town Limit          | -150+00 to 0+00    | 84                             |  |
| 2017 Sand Placement Area (Skyline Road to Asheville Street)                      | -20+00 to 320+05   | 103                            |  |
| Northern Section of Southern Shores from 5th Avenue North to Northern Town Limit | -197+12 to -157+41 | 57                             |  |



#### **Updated numbers based on June 2020 Data**

| Beach Section  | Profile Stations   | Average Useable Beach<br>Width |  |
|--|--------------------|--------------------------------|--|
| Town of Southern Shores from 3rd<br>Avenue South to Southern Town Limit                | -150+00 to 0+00    | 69                             |  |
| Northern Section of Southern Shores<br>from 5th Avenue North to Northern Town<br>Limit | -197+12 to -157+41 | 69                             |  |

#### **Volume Change (Update):**

- North Section:
  - > Average volume change rate of +6.1 cy/ft./yr. between Dec. 2017 and June 2020
  - Average volume change rate of -0.2 cy/ft./yr. between Sept. 2013 and June 2020 (6.75 years) along northern 2,000 feet of Town (Area north of 9<sup>th</sup> Ave.)
- Central Section Average volume change rate of -0.3 cy/ft./yr (Dec. 2017 to June 2020) and +2.7 cy/ft./yr (Oct. 2006 to June 2020)
- South Sections Average volume change rate of -15.3 cy/ft./yr (Dec. 2017 to June 2020) and +0.3 cy/ft./yr (Oct. 2006 to June 2020) Note: Includes beach nourishment
- Overall Average along Central and South Section was -5.2 cy/ft./yr, an increase from -3 cy/ft./yr reported in 2019.



## Project Volumes: Beach Management Addendum A

Table 2. Comparison of volumes calculated for each of the beach fill options

| Design                  | Design<br>Volume <sup>(1)</sup> | Diffusion<br>Loss Volume | Advanced Fill<br>Volume (3) | Taper<br>Volume (4) | Total<br>Volume | Avg. Fill<br>Density (5) |
|-------------------------|---------------------------------|--------------------------|-----------------------------|---------------------|-----------------|--------------------------|
| Option 1 <sup>(6)</sup> | 540,000                         | 54,400                   | 225,000                     | 9,000               | 828,400         | 36                       |
| Option 2                | N/A - De                        | esign Volumes an         | d Transition Area           | Volumes are t       | the Same as C   | option 1.                |
| Option 3 <sup>(6)</sup> | 720,000                         | 68,800                   | 225,000                     | 12,000              | 1,025,800       | 48                       |
| Option 4                | 591,400                         | 54,400                   | 225,000                     | 7,500               | 878,300         | 30                       |
| Option 5                | 681,400                         | 54,400                   | 225,000                     | 7,500               | 968,300         | 35                       |

<sup>(1)</sup> Volume (CY) necessary to achieve the design goal of each option. This number excludes diffusion loss, advanced fill, and tapers.




<sup>(2)</sup> Volume (CY) included to account for diffusion losses and background erosion (APTIM, 2018).

<sup>(3)</sup> Volume (CY) included to account for background erosion expected to occur throughout the nourishment interval. Re-nourishment interval assumed to be 5 years.

<sup>(4)</sup> Volume (CY) to construct a 500-foot taper on the northern end of the beach fill. Taper is dependent on the fill density at the northern extent of the project.


<sup>(5)</sup> Total Volume included in the Design Volume divided by the length of the beach fill (CY/FT).

<sup>&</sup>lt;sup>(6)</sup> Options that only include placement of beach fill south of 3<sup>rd</sup> Avenue.




**Pre-Project Conditions** 






**Initial Construction** 






**Equilibration of Beach Fill** 






**Nourishment Interval** 





**Nourishment Interval** 





**Maintenance = Beach Renourishment** 



## Project Costs: Beach Management Addendum A

#### Table 3. Project Option Cost Estimates

| Option | Permitting/<br>Design Soft<br>Cost <sup>(1)</sup> | Volume (cy) | Construction<br>Cost <sup>(3)</sup> | Construction<br>Soft Cost <sup>(4)</sup> | Construction<br>Env.<br>Monitoring<br>Costs <sup>(5)</sup> | Contingency<br>Cost (10%) | TOTAL COST   |
|--------|---|-------------|-------------------------------------|--|--|---------------------------|--------------|
| 1      | \$435,000   | 828,400     | \$11,758,000                        | \$235,500 <sup>(6)</sup>                 | \$275,300  | \$1,270,400               | \$13,974,200 |
| 3      | \$435,000   | 1,025,800   | \$14,146,000                        | \$255,500                                | \$332,400  | \$1,516,900               | \$16,685,800 |
| 4      | \$435,000   | 878,300     | \$12,505,000                        | \$241,500                                | \$232,700  | \$1,341,400               | \$14,755,600 |
| 5      | \$435,000   | 968,300     | \$13,783,000                        | \$249,500                                | \$256,600  | \$1,472,400               | \$16,196,500 |

<sup>(1)</sup> Professional services costs associated with the permitting and design of the beach fill project. These costs include design surveys of the beach and offshore sand investigations.



<sup>(2)</sup> Total volume (CY) estimated for the Option including design volume, diffusion losses, advanced fill, and tapers.

<sup>(3)</sup> Costs associated with mobilization/demobilization, sand placement, and other costs paid directly to the dredge contractor.

<sup>(4)</sup> Costs associated with development of construction bid package, bidding assistance, and construction administration.

<sup>(5)</sup> Costs anticipated for estimated environmental monitoring that may be required by permit condition.

<sup>(6)</sup> Updated Construction Soft Costs from those included in the September 2019 update. The updating of these cost estimates resulted in a slight decrease in the Total Cost estimate.

#### **Schedule:**

| Milestone  | Start Date    | Completion<br>Date | Number of<br>Months |
|--|---------------|--------------------|---------------------|
| Project Initiation / Interagency Meeting           | April 2020    | April 2020         | 1                   |
| Borrow Area Development                            | May 2020      | January 2021       | 9                   |
| Engineering Design                                 | June 2020     | April 2021         | 11                  |
| Federal Permitting                                 | April 2020    | June 2021          | 15                  |
| State Permitting                                   | February 2021 | July 2021          | 6                   |
| Development of Construction Plans & Specifications | March 2021    | June 2021          | 4                   |
| Solicitation of Bids                               | June 2021     | July 2021          | 1.5                 |
| Award Construction Contract                        | July 2021     | August 2021        | 1.5                 |
| Construction                                       | May 2022      | October 2022       | 5                   |



